OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, MYSORE.

Notification dated the 6th Jaunary 1937.

Sealed tenders, in triplicate will be received at the office of the Superintendent, Power and Lighting, Mysore. Tenders should be superscribed with the name of the work given below :—

2. The plans may be seen in the office of the undersigned at all working hours.

3. The tenders should be drawn in conformity with the specifications furnished below writing out the rates at which different items of work will be executed, in figures as well as in words failing which the tenders will be disqualified.

4. The undersigned reserves the right to reject the tenders without assigning any reason therefor.

5. The successful tenderer will be required to deposit with the undersigned an earnest money of Rs. 40 and execute an agreement within 3 days from the date of receipt of intimation as to the acceptance of the tender, failing which the tender will be disposed of otherwise.

6. The materials to be used on the work should be either best quality English or American manufacture and conform to the specifications. The work should be executed strictly in accordance with the wiring rules of this Department as well as the Institution of Electrical Engineers. Mention should also be made of the catalogue numbers of the materials offered.

7. No items other than those noted in the statement should be included in the tender as the items include provision for the masonry repairs, painting, etc.

8. The successful tenderer should carry out any changes that might be suggested during the progress of the work with regard to the location of the fixtures, switch-points, etc., without extra cost if the estimate is not materially affected by such a deviation.

9. Name of work—"Installing Electric Lights, etc., to the Travellers' Bungalow and Out-houses at Shimoga."

10. Last date and time of receiving the tender is 25th January 1937 at 3 P.M.

11. Time and date of opening the tenders in public is at 4-30 P.M. on 25th January 1937.

12. The time allowed for the completion of the work is four weeks from the date of acceptance of the tender, failing which a penalty of annas two for each day's delay over and above the stipulated time will be enforced.

13. Details of work :—

	PART I—*Main Building (Exterior work).*	Quantity.
1.	Supplying and fixing S.M. Rail 24 ft., long and tarring the same ..	1
2.	Do do 2-pin D.C.A. complete for rail	2
3.	Do do 4- pin outrigger complete with bolts etc., ..	1
4.	Do do 4-pin D.C.A. complete with brace clamps, braces, etc., ...	1
5.	Do do Insulators and pins	14
6.	Do and stringing bare copper wire No. 8 B. & S. ..	130 ft.
7.	Do guy sets complete with anchor, rod, 7-strand guy wire ..	2
8.	Supplying and running mains in ¾" W.I. pipe with necessary bends, complete with clamps, etc., using No. 10 B. & S. 2,500-megohms grade insulated wire	25 ft.
9.	Earthing	Item.
	Interior.	
1.	Supplying, fixing and wiring varnished T.W. Board 24"×18"×1" with battens and rear board equipping it with a 30-amp. D.P.S.T. iron-clad switch with fuses, one "Neata" 10-amp. per way 5-way distribution box with 10-amp. circuit switches with bakelite cover, using No. 10 and 12 B. & S. 2,500-megohms grade insulated wire and accessories. ..	1
2.	Supplying, fixing and wiring in T.W. 2"×1" two-way casing treated with 2-coats of shellac varnish for drop lights complete with 2-plate ceiling rose (bakelite), flexible cord, B.C.C.G. lampholder (reinforced bakelite), 5 amp. reinforced bakelite tumbler switch, one 5-amp. bow cutout, etc., using No. 12 and 14 B. & S. 2,500-megohms grade insulated wire for mains and taps, respectively and accessories	8
3.	Do do braized conduit pendants 18"×⅝", complete with brass stout ceiling plate, reinforced B.C. lampholder, etc., as per specification above	3
4.	Do do for reinforced bakelite B.C. batten lampholders complete as per specification above	4
5.	Do do Bulkhead fittings complete with B.C. lampholder, enamelled reflector, etc., as per specification above ..	4
6.	Do do for oxidized copper brackets 6"×½" complete	

		Quantity.
7.	Supplying and fixing shades white opal 10"	24
8.	Do do lamps 230-volts, B.C., 20-60 watts	28

PART II—*Installing Lights in the two Kitchens and Out-houses.*

1.	Supplying and fixing S.M. Rail 24-ft. long and tarring the same	2
2.	Do do 2-pin D.C.A. complete	2
3.	Do do 2-pin outrigger complete with bolts, etc.,	1
4.	Do do insulators and pins	16
5.	Do do guy sets complete with anchor, rod and 7-strand guy wire	2
6.	Supplying and stringing bare copper wire No. 8 B. & S.	260 ft.
7.	Supplying and running mains in ½" W.I. pipe with bends, etc., using No. 14 B. & S. insulated wire, 2,500-megohms grade and accessories	60 ft.
8.	Earthing	Item.
9.	Supplying, fixing and wiring varnished T.W. Board 8"×8"×1" with battens and rear board, equipping it with a D.P. 5-amp. linked switch and a pair of 5-amp. bow cutouts using No. 14 B. & S. 2,500-megohms grade insulated wire and accessories	4
10.	Supplying, fixing and wiring in T.W. 2"×1" two way casing treated with 2-coats of shellac varnish for drop lights complete with reinforced bakelite 2-plate ceiling rose, flexible cord, reinforced B.C.C.G. lampholder, 5-amp. reinforced bakelite switch, one 5-amp. bow cutout using No. 14 B. & S. 2,500-megohms grade insulated wire and accessories	7
11.	Do do for reinforced B.C. batten lampholder complete as per specification above	1
12.	Supplying and fixing shades, tin enamelled 10"	8
13.	Do do lamps 230-volts, B.C. 20 to 60 watts.	8

Notification dated the 11th January 1937.

Sealed tenders, in triplicate, will be received at the Office of the Superintendent, Power and Lighting, Mysore. Tenders should be superscribed with the name of the work given below :—

2. The plans may be seen in the office of the undersigned and that of the Assistant Superintendent, C. P. S. Bhadravathi, at all working hours.

3. The tenders should be drawn up in conformity with the specifications furnished below writing out the rates at which the different items of work will be executed, in figures as well as in words, failing which the tenders will be disqualified.

4. The undersigned reserves the right to reject the tenders without assigning any reason therefor.

5. The successful tenderer will be required to deposit with the undersigned an earnest money of Rs. 60 (sixty), and execute an agreement within 3 days from the date of receipt of intimation as to the acceptance of the tender, failing which the tender will be disposed of otherwise.

6. The materials to be used on the work should be either best quality English or American manufacture and conform to the specifications. The work should be executed strictly in accordance with the wiring rules of this Department as well as that of the institution of Electrical Engineers. Mention should also be made of the catalogue numbers of the materials offered.

7. No items other than those noted in the statement should be included in the tender as the items include provision for masonry repairs, painting, etc.

8. The successful tenderer should carry out any changes that might be suggested during the progress of the work, with regard to the location of the fixtures, switch-points, etc., without extra cost if the estimate is not materially affected by such a deviation.

9. *Name of work.*—Installing electric lights to the Circuit House, etc., at Shimoga.

10. Last date and time of receiving the tenders is 30th January 1937 at 3 P.M.

11. Time and date for opening the tenders in public is 4-30 P.M., on 30th January 1937.

12. The time allowed for the completion of the work is six weeks from the date of acceptance of the tender, failing which a penalty of annas two for each day's delay over and above the stipulated time will be enforced.

13. Details of work.—

No.	Description	Quantity
	PART I—EXTERIOR.	
1	Supplying and laying No. 8 B. & S. twin conductor V. I. R. insulated, lead covered, double steel tape armoured, jute served underground cable for 600-V pressure in a trench 3-feet deep surrounding the same with 3" of fine sand and enclosing the ends of the cable in C. I. pole and indoor type junction boxes filled with bitumen and providing 18-feet of 2" galvd. pipe with a bend at the pole end; using suitable clamps and accessories	200 feet.
	PART II—INTERIOR MAIN BUILDING.	
1	Supplying and running main in ¾" W. I. pipe embedding the same in the wall using No. 8 B. & S. 2500-megohms grade insulated wire and accessories	6 feet.
2	Earthing the main pipe, etc.	Item
3	Supplying, fixing and wiring a T. W. board 24"×18"×1" with battens and rear board, equipping it with a 4-way D. P. H. O. pattern "Neata" 10-amp. per way distribution box with 10-amp. bakelite circuit switches, one 30-amp. D. P. iron-clad switch with fuses, using No. 8, 10 and 12 B. & S. 2500-megohms grade insulated wire and accessories	1
4	Supplying and wring in No. 14 B. & S. twin and triple conductor lead cable with bonded wire complete with universal metal junction boxes, etc., for "Walton" fittings complete with chain, canopy, B. C. lamp-holder, 14" opal globe, etc., using reinforced bakelite 2-plate ceiling rose, 5-amp. tumbler switch with cream bakelite cover, one 3-amp. bow cutout and accessories	3
5	Do do for "Benflux" fittings complete as above	3
6	Do do for drop lights complete as above	4
7	Supplying and wiring as per item No. 4 for Bulkhead fittings complete with enamelled reflector, etc.	2
8	Do do reinforced B. C. batten bakelite lampholders complete as above	5
9	Do do for ⅜" braized conduit pendants 18" long complete with stout brass ceiling plate, B. C. lampholder, etc., as above	3
10	Do do for reinforced bakelite combined wallplug and switch 5-amp. with nipple complete as above	3
11	Supplying and wiring for water-tight fittings complete with gooseneck, wellglass, B. C. lampholder as above	2
12	Supplying and fixing shades, green and white opal	12
13	Do do lamps 20-60 watts 230-V. B. C.	19
14	Do do 100-watts do	3
15	Earthing	Item
16	Supplying and fixing lamplocks	15
	PART III—INSTALLATION OF GOOSENECK LAMP FITTING IN THE YARD.	
1	Supplying, fixing and wiring a goose neck lamp fitting on a S. M. Rail complete with radial wave reflector, hood, B. C. lampholder, etc., using No. 14 B. & S. insulated wire, 75-feet of No. 12 B. & S. twin conductor V. I. R. lead covered double steel tape armoured, jute served, underground cable for 600-volts pressure, laid 3 feet underground surrounded with 3" of fine sand and provided at the ends with C. I. Indoor and pole junction boxes filled with compound and enclosed at the pole end with suitable size galvd. pipe, bends, etc., and accessories (Gooseneck fitting complete only will be supplied by this Department)	1
2	Supplying, fixing and wiring T. W. board 9"×9" with battens and rear board, equipping it with a D. P. 5-amp. linked switch protected with a pair of 5 amp. fuse cutouts using necessary accessories	1
3	Earthing	Item

No.	Description	Quantity
	PART IV—INSTALLATION OF LIGHTS TO THE KITCHEN & CLUB ROOM.	
1	Supplying and laying No. 12 B. & S. twin conductor V. I. R. insulated, lead covered, double steel tape armoured, jute served, underground cable for 600-V pressure in a trench 3 feet deep, surrounding the same with 3" of fine sand and enclosing the ends of the cable in C. I. Indoor type junction boxes filled with bitumen using necessary accessories ..	135 feet.
2	Supplying, fixing and wiring a T. W. board 9"×9" with battens and rear board equipping it with a D. P. 5-amp. linked switch protected with a pair of 5-amp. fuse cutouts using necessary accessories	2
3	Supplying, fixing and wiring in twin and triple conductor No. 14 B. & S. lead-covered cable with bonded wire for drop lights complete with 2-plate reinforced bakelite ceiling rose, flexible cord, B. C. lampholder, 5-amp. tumbler switch with bakelite cover, one 3 amp. bow cutout using Universal metal junction boxes and accessories	4
4	Do do for braized conduit pendants 18"×⅝" with stout brass ceiling plate, B. C. lampholder, etc., as above	1
5	Do do for reinforced bakelite combined wall plug and switch 5-amp. with nipple as above	1
6	Do and fixing shades Langham 10"	5
7	Do do lamps 20-60 watts, 230 volts, B. C.	5
8	Earthing	Item.

A. C. MUNIRATHNAM,
Superintendent.

MYSORE RAILWAYS.

OFFICE OF THE CHIEF STORE KEEPER, MYSORE RAILWAYS, MYSORE SOUTH.

Abstract Notification

The attention of the public is invited to Sale Notification No. 13, calling for tenders for the purchase of valuable scrap metal, published on page 55 of Part VI of the *Mysore Gazette*, dated 14th January 1937.

A. SADASIVAN,
Chief Store Keeper.

OFFICE OF THE ASSISTANT ENGINEER, HEAD QUARTER RANGE, MYSORE.

Abstract Notification dated the 5th January 1937.

The attention of the public is invited to the detailed notification calling for tenders for the construction of the District Board Office at Mysore, published in pages 34-40, Part VI of the *Mysore Gazette*, dated 7th January 1937. The earnest money to be deposited along with the tender is Rs. 4,000 which may be in the form of cash or Government Promissory Notes or Bonds and Postal cash certificates or Savings Bank Deposit Accounts, but not in any other form.

The latest date and hour for the receipt of Tenders will be 22nd January 1937 at 12 Noon.

M. A. RAMANUJAM,
Assistant Engineer.

GOVERNMENT TRAINING COLLEGE, MYSORE.

Notification dated 11th January 1937.

It is hereby notified for the information of the public that the undermentioned manufactured articles of the Practical Instruction class attached to the Practising Kannada Middle School, Mysore (Government Training College), will be sold by public auction on Wednesday the 3rd March 1937 at 4 P.M. at the premises of the Government Training College, Mysore.

The highest bid at each auction will be accepted. The full amount of the highest bid accepted must be paid on the spot and arrangements made to remove the things immediately. In all matters of dispute the decision of the Principal is final.